

TENDER NOTICE

No.585/PAJ/EC/2022.

Date: - 11-02-2022

Sub: PAJANCOA&RI – Engineering Cell - Providing flood light arrangement to the volley ball court in PAJANCOA & RI, Karaikal - Tenders – Invited – Reg.

Sealed tenders are invited by the undersigned from the reputed firms for the following works adopting two-bid system (technical bid and financial bid) for "Providing flood light arrangement to the volley ball court in PAJANCOA & RI, Karaikal"

S.No.	Name of the item	Quantity	Bid Security Amount (Rs.) (Earnest Money Deposit)
1	17.2.9 Supply and erection of MS swaged tublar pole with base plate and single ornamental bracket two coats of zinc chromate and two coats of aluminium / epoxy painting. Pole height 6mt. Pole dimension - 114.3 x 3.65 x 3000mm, 88.9 x 3.25 x 1750mm; 76.10 x 3.25 x 1250mm bracket dimension 48.3 x 3.25 x 2700mm - 1no, base plate dimension 250 x 250 x 5mm. Overall height 7.5 mt. Including excavation of earth 750 x 750 x 1650mm and cement concrete 1: 2 : 4 750 x 750 x 1650mm for filling and capping above ground level 450mm dia x 600mm height. One coat of zinc chromate and two coat of aluminium/epoxy painting should be done after erection of the pole and inclusive of suitable length 1.25mt.- 2 nos. of 40mm dia medium class GI pipe for cable raising.	6 Nos	An amount of Rs.5,000/- towards EMD drawn favour of the Dean, PAJANCOA & RI, payable at Karaikal should be enclosed along with technical bid.
2.	Supply and fixing of 100W LED Flood light(IP 68 WATER PROOF) in the street light post with required bolts and nuts complete. Make. Sterlite	6 Nos	
3.	Supply and fixing of sintex terminal box in the street light post with necessary bolts and nuts.	6 Nos	
4.	Supply of 4 core 16 sqmm U.G cable. Make : Paragon/Empire/ Suncab/ Finolex.	100.00 Metre	
5.	7.1.1 Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 kV grade of following size direct in ground including excavation , sand cushioning, protective covering and refilling the trench etc.as required - Upto 35 sq.mm	100.00 Metre	
6.	Supply and drawing of 3 core 2.5 sqmm copper wire from sintex terminal box to flood light fitting.Make : Finolex/ Kunden/ Havells.	50.00 Metre	
7.	Supply and fixing of 63A cubical switch with SS enclosure with necessary bolts and nuts in the exisiting boys hostel pillar box.	1 No	
8.	9.1.33 Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1kV grade as required - 4 X16 sq.mm (28 mm)	13 Sets	

Along with this tender notice, terms and conditions, tender schedule (technical bid) with specifications, tender schedule (financial bid) are available in the institute's website www.pajancoa.ac.in which can be downloaded.

In case of any difficulty in downloading the bidding documents from the website www.pajancoa.ac.in, the prospective bidders may please contact the undersigned.

To

www.pajancoa.ac.in


DEAN
DEAN
PAJANCOA & RI,
KARAIKAL - 609 603.

1. Tender schedule (Technical bid) consists of all technical details along with commercial terms and conditions; and Tender schedule (Financial bid) is for indicating price for the items mentioned in the technical bid. The technical bid and the financial bid should be respectively. Both these sealed covers are to be put in a bigger cover which should also be sealed and duly superscribed as "**TENDER BID FOR THE** "Providing flood light arrangement to the volley ball court in PAJANCOA & RI, Karaikal " and addressed to the **Dean, Pandit Jawaharlal Nehru College of Agriculture and Research Institute, Karaikal-609603**. The duly completed tender forms in all respects should be submitted on or before **4:30 pm on 28-02-2022**. Tender forms received after the due date and time will summarily be rejected. The technical bids will be opened the institute at the first instance and evaluated. At the second stage financial bids of only the technically acceptable offers will be opened for further evaluation and awarding the contract.
2. Tender cost, Bid security (Earnest Money Deposit) as indicated in the tender notice have to be paid, as demand draft drawn in favour of Dean, Pandit Jawaharlal Nehru College of Agriculture and Research Institute, payable at Karaikal along with the technical bid. Technical bid without tender cost, bid security will summarily be rejected.
3. The tender should be valid for six months from the date of the opening. The rate should be quoted for each item with specification and model if applicable and should be indicated clearly both in words and figures. Any scoring or overwriting should be attested by the tenderers with full signature.
4. Tenders will be opened at 5:00 pm on the same day in the presence of bidders or their authorized representatives who choose to be present at the time of opening. If the opening day of the tender happens to be a holiday the tender will be opened on the next working day at the same time specified.
5. Performance security @ 5% of the material value should be paid by the successful bidder in the form of account payee demand draft or fixed deposit receipt from a commercial bank before executing the order. Performance security to be paid should remain valid for a period of sixty days beyond the date of completion of warranty obligations.
6. The material should be supplied strictly in accordance with the specifications given and should fulfill the successful tests carried out in the institute. The supply and installation should be made as per the supply order to be sent by the Dean.
7. The rate should be FOR destination and should include all charges such as packing, forwarding, etc. including loading / unloading. The insurance charges, if any, are to be borne by the suppliers.
8. The Dean reserves the right to reject or accept any tender without assigning any reason thereof.

9. The institute is eligible for exemption of Central excise and customs duty. However custom duties at Indian port, if any, will be borne by the institute and will be paid in Indian rupees only. Hence, the item price may be quoted separately (i.e.) unit price & taxes, etc.
10. Satisfactory installation and test running at the institute is to be done at the cost of supplier.
11. The materials should be supplied within two months from the date of supply order.
12. The material covered under the supply order, when installed, shall be warranted for the quality, workmanship, trouble free operation and performance for a period of one year from the date of putting the system into operation at the institute. If any item covered under warranty fails, the same shall be replaced at free of cost including all the applicable charges and shipping cost both ways.
13. Complete technical specifications, supported with literature, are to be included with the quotation. Manufacturers of various major parts/equipment must be mentioned explicitly.



DEAN
PAJANCOA&RI
Karaikal - 609 603

1. Asp (Education) for n/a.

TENDER SCHEDULE

(Technical Bid)

Tender Notice No: 585/PAJ/EC/2022

Name of the item: Providing flood light arrangement to the volley ball court in PAJANCOA & RI, Karaikal

SL. No.	Specifications and features		Whether complied (Yes / No)	If yes, please attach technical literature, if any
1.	17.2.9 Supply and erection of MS swaged tubular pole with base plate and single ornamental bracket two coats of zinc chromate and two coats of aluminium / epoxy painting. Pole height 6mt. Pole dimension - 114.3 x 3.65 x 3000mm, 88.9 x 3.25 x 1750mm; 76.10 x 3.25 x 1250mm bracket dimension 48.3 x 3.25 x 2700mm - 1no, base plate dimension 250 x 250 x 5mm. Overall height 7.5 mt. Including excavation of earth 750 x 750 x 1650mm and cement concrete 1: 2 : 4 750 x 750 x 1650mm for filling and capping above ground level 450mm dia x 600mm height. One coat of zinc chromate and two coat of aluminium/epoxy painting should be done after erection of the pole and inclusive of suitable length 1.25mt.- 2 nos. of 40mm dia medium class GI pipe for cable raising.	6 Nos		
2.	Supply and fixing of 100W LED Flood light(IP 68 WATER PROOF) in the street light post with required bolts and nuts complete. Make. Sterlite	6 Nos		
3.	Supply and fixing of sintex terminal box in the street light post with necessary bolts and nuts.	6 Nos		
4.	Supply of 4 core 16 sqmm U.G cable. Make : Paragon/Empire/ Suncab/ Finolex.	100.00 Metre		
5.	7.1.1 Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 kV grade of following size direct in ground including excavation , sand cushioning, protective covering and refilling the trench etc.as required - Upto 35 sq.mm	100.00 Metre		
6.	Supply and drawing of 3 core 2.5 sqmm copper wire from sintex terminal box to flood light fitting.Make : Finolex/ Kunden/ Havells.	50.00 Metre		
7.	Supply and fixing of 63A cubical switch with SS enclosure with necessary bolts and nuts in the existing boys hostel pillar box.	1 No		
8.	9.1.33 Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1kV grade as required - 4 X16 sq.mm (28 mm)	13 Sets		

Number of the demand draft enclosed towards bid security / EMD Deposit

Commercial terms and conditions:

1. Delivery:
2. Installation:
3. Validity:
4. Others if any:

I / We have carefully read the terms and conditions of the Tender and agree to abide by these in letter and spirit. I / We agree to forfeit of the bid security (earnest money) if I / We fail to comply with any of the terms and conditions in whole or in part laid down in the Tender forms.

Date:

Signature of the Bidder

Office Stamp

Name in block letters

TENDER SCHEDULE**(Financial Bid)****Tender Notice No: 585/PAJ/EC/2022****Name of the item:** Providing flood light arrangement to the volley ball court in PAJANCOA & RI, Karaikal

S.No.	Description of the item	Quantity	Rate (Rs.)	Amount (Rs.)
1	17.2.9 Supply and erection of MS swaged tubular pole with base plate and single ornamental bracket two coats of zinc chromate and two coats of aluminium / epoxy painting. Pole height 6mt. Pole dimension - 114.3 x 3.65 x 3000mm, 88.9 x 3.25 x 1750mm; 76.10 x 3.25 x 1250mm bracket dimension 48.3 x 3.25 x 2700mm - 1no, base plate dimension 250 x 250 x 5mm. Overall height 7.5 mt. Including excavation of earth 750 x 750 x 1650mm and cement concrete 1: 2 : 4 750 x 750 x 1650mm for filling and capping above ground level 450mm dia x 600mm height. One coat of zinc chromate and two coat of aluminium/epoxy painting should be done after erection of the pole and inclusive of suitable length 1.25mt.- 2 nos. of 40mm dia medium class GI pipe for cable raising.	6 Nos		
2	Supply and fixing of 100W LED Flood light(IP 68 WATER PROOF) in the street light post with required bolts and nuts complete. Make. Sterlite	6 Nos		
3	Supply and fixing of sintex terminal box in the street light post with necessary bolts and nuts.	6 Nos		
4	Supply of 4 core 16 sqmm U.G cable. Make : Paragon/Empire/ Suncab/ Finolex.	100.00 Metre		
5	7.1.1 Laying of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 kV grade of following size direct in ground including excavation , sand cushioning, protective covering and refilling the trench etc.as required - Upto 35 sq.mm	100.00 Metre		
6	Supply and drawing of 3 core 2.5 sqmm copper wire from sintex terminal box to flood light fitting.Make : Finolex/ Kunden/ Havells.	50.00 Metre		
7	Supply and fixing of 63A cubical switch with SS enclosure with necessary bolts and nuts in the existing boys hostel pillar box.	1 No		
8	9.1.33 Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1kV grade as required - 4 X16 sq.mm (28 mm)	13 Sets		
The rate shall be quoted inclusive of GST.				
TOTAL				

I / We have carefully read the terms and conditions of the Tender and agree to abide by these in letter and spirit. I / We agree to forfeit of the bid security (earnest money). if I / We fail to comply with any of the terms and conditions in whole or in part laid down in the Tender forms.

Date:

Signature of the Bidder

Office Stamp

Name in block letters