



**PANDIT JAWAHARLAL NEHRU COLLEGE OF AGRICULTURE AND RESEARCH
INSTITUTE**

(Sponsored by Govt. of Puducherry and Affiliated to Pondicherry University, Puducherry)

SERUMAVILANGAI, NEDUNGADU (POST), KARAİKAL - 609 603

**Dr. A. POUCHEPPARADJOU, Ph.D.,
DEAN**

Phone : 04368 - 261372

Fax : 04368-261260

Email : pajancori.kkl@nic.in

QUOTATION CALL LETTER

No: 714 /PAJ/EC/2022

Date: 09-11-2022

Sir,

Sub: PAJANCOA&RI – Engineering Cell – Supply of required materials and construction of casing and substrate preparation room for the Department of Plant Pathology of PAJANCOA & RI at Sorakudy, Karaikal – Quotations – called for – Reg.

This institute has proposed to construct a Galvalume sheet roof steel structure as casing and substrate preparation room for the Department of Plant Pathology at the premises of PAJANCOA &RI Sorakudy Karaikal as per the specifications given below.

Sl No.	Item	Specification	Quantity Required.
1.	Galvalume sheet roof steel structure.	10.16.2 Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting , hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete - hot finished seamless type tubes including cost civil works for foundation- all as directed by the Engineer in charge.	450.00 Kg
2.		12.51.1 Providing and fixing pre-coated galvanised steel sheet roofing accessories 0.5mm (+0.05%) total coated thickness , zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both sides of the sheet and polyester top coat 15-18 microns using self drilling / self tapping screws complete - Ridges plain (500 - 600mm)	7.00 metre
3.		12.80 Providing and fixing colour coated galvalume sheet of 550 M.P.A. yield of AZ 150 strength formed as per patterned steel rib profile with the depth of 31 mm pitch of 250 mm and overall width of 1060 mm and thickness 0.5mm with required J or C hook bolts and nuts 8mm dia G.S.paint and working etc., complete excluding the cost of purlin , rafter and truss etc.,	40.00 Sqm
4.		13.52.1 Finishing with epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface ,etc. complete - on steel work	40.00 Sqm

You are requested to quote your lowest rate for the construction of casing and substrate preparation room for the Department of Plant Pathology of PAJANCOA & RI at Sorakudy, Karaikal including supplying of required materials and construction with above mentioned specifications. The quotation should be addressed to the DEAN, PAJANCOA & RI,, Nedungadu P.O, Karaikal – 609 603 and should be sent in a sealed cover super scribed as "QUOTATION FOR THE WORK OF Construction of casing and substrate preparation room for the Department of Plant Pathology of PAJANCOA & RI at Sorakudy, Karaikal" with due date and time. The quotation should reach this office on or before 4.30 pm on 23-11-2022

Thanking you

Yours faithfully

DEAN.

1414