



PANDIT JAWAHARLAL NEHRU COLLEGE OF AGRICULTURE AND RESEARCH INSTITUTE

(Govt. of Puducherry Institution and Affiliated to Pondicherry University, Puducherry)

SERUMAVILANGAI, NEDUNGADU (POST), KARAIKAL - 609 603

**Dr. A. Poucheparadjou, Ph.D.,
DEAN**

Phone : 04368 - 261372

TeleFax : 04368-291260

Email : pajancori.kkl@nic.in

QUOTATION CALL LETTER

No: 1344/11/PAJ/EC/2023

Date: 22.03.2023

Sir,

Sub: PAJANCOA&RI – Engineering Cell- Providing Cement Concrete Flooring in front of seed storage godown-Quotations – Called for – Reg.

This Institute has proposed to construct Cement Concrete Flooring in front of seed storage godown as per the specifications given below:

Sl. No.	Item	Specification(s)	Quantity required	Rate	Per	Amount
1.	Construction of Cement Concrete Flooring in front of seed storage godown	2.8.1 Earthwork in excavation by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 Sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m - all kinds of soil.	25.00 cum		Cum	
2.		4.1.10 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering- all work upto plinth level- 1:5:10 (1 cement : 5 coarse sand :10 graded stone aggregate 40 mm nominal size)	15.00 cum		Cum	

3.	2.27A.1 Supplying and filling with gravel (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth consolidating each deposited layers by ramming and watering etc. complete including all lead and lift	7.00 Cum	Cum
4.	6.2.2 Brick work with common burnt clay modular bricks of class designation 7.5 in foundation and plinth in – cement mortar 1:6 (1 Cement : 6 Coarse sand)	2.00 Cum	Cum
5.	11.3.1 Cement concrete flooring 1:2:4 (1 Cement : 2 Coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement slurry, but excluding the cost of nosing of steps etc complete – 40 mm thick with 20mm nominal size stone aggregate	135.00 Sqm	Sqm.
6.	Add. GST		

You are requested to quote your lowest rate for the Construction of Cement Concrete Flooring in front of seed storage godown for PAJANCOA & RI at Surakudy, Karaikal. The quotation should be addressed to the DEAN, PAJANCOA & RI, Nadungadu (Post), Karaikal – 609 603 and should be sent in a sealed cover superscribed as **“QUOTATION FOR THE WORK OF CONSTRUCTION OF CEMENT CONCRETE FLOORING IN FRONT OF SEED STORAGE GODOWN for PAJANCOA & RI at Surakudy, Karaikal”** with due date and time. The quotation should reach this office on or before **4.30 pm on 05.04.2023.**

Yours faithfully


DEAN 29/3

To PAJANCOA & RI Website : www.pajancoa.ac.in

N. / 27/3/23/4
Forwarded To Dr. Saravanan.S ASP(CS)
To Upload In Website