



**PANDIT JAWAHARLAL NEHRU COLLEGE OF AGRICULTURE AND RESEARCH  
INSTITUTE**

(Sponsored by Govt. of Puducherry and Affiliated to Pondicherry University, Puducherry)  
SERUMAVILANGAI, NEDUNGADU (POST), KARAİKAL - 609 603

**Dr. A. POUCHEPPARADJOU, Ph.D.,**  
**DEAN**

Phone : 04368 - 261372  
Fax : 04368-261260  
Email : pajancori.kkl@nic.in

**QUOTATION CALL LETTER**

No: 1377/PAJ/EC/2023

Date: 06-04-2023

Sir,

**Sub:** PAJANCOA&RI – Engineering Cell – Demolish and reconstruct existing dilapidated compound wall at frontage of eastern premises (behind the Department of Horticulture farm office) of PAJANCOA&RI, Karaikal– Quotations – called for – Reg.

\*\*\*\*\*

This institute has proposed to Demolish and reconstruct existing dilapidated compound wall at frontage of eastern premises (behind the Department of Horticulture farm office) of PAJANCOA&RI, Karaikal, as per the specifications given below.

SI No.	Item	Specification	Quantity Required.	Rate	Per	Amount
1.		15.7.4 Demolishing brick work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead - in cement mortar	4.50 Cum			
2.	Demolish and reconstruct existing dilapidated compound wall at frontage of eastern premises (behind the Department of Horticulture farm office)	6.4.2 Brick work with common burnt clay F.P.S (non modular ) bricks of class designation 7.5 in superstructure above plinth level upto floor five level in all shapes and sizes in - cement mortar 1:6 ( 1 cement : 6 coarse sand)	3.00 Cum			
3.		6.13.1 Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level upto floor V level - cement mortar 1:3 (1 cement : 3 coarse sand)	42.00 Sqm			
4.		13.2.1 15mm cement plaster on the rough side of single or half brick wall of mix - 1:4 (1cement : 4 fine sand)	130.00 Sqm			
5		13.46.1 Finishing walls with acrylic smooth exterior paint of required shade - New work (two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg / 10 sqm	130.00 Sqm			
6.			Add GST			

(P.T.O)

You are requested to quote your lowest rate for Demolish and reconstruct existing dilapidated compound wall at frontage of eastern premises (behind the Department of Horticulture farm office) of PAJANCOA&RI, Karaikal. The quotation should be addressed to the DEAN, PAJANCOA & RI,, Nedungadu P.O, Karaikal – 609 603 and should be sent in a sealed cover super scribed as "QUOTATION FOR THE WORK OF DEMOLISHING AND RECONSTRUCTION OF COMPOUND WALL" with due date and time. The quotation should reach this office on or before 4.30 pm on 21-04-2023

Thanking you

Yours faithfully

  
DEAN. 10/4/23

To

1. The Superintending Engineer, Circle III, Public Works Department, Karaikal.
2. The Commissioner, Thirunallar Commune, Thirunallar.
3. The Commissioner, Nedungadu Commune, Nedungadu,
4. The Commissioner Karaikal Municipality, Karaikal.
5. www.pajanca.ac.in

N. 1/11/4/23 Jr  
Forwarded To Dr. Saravanan.S ASP(CS)  
To Upload In Website