



**PANDIT JAWAHARLAL NEHRU COLLEGE OF AGRICULTURE AND RESEARCH
INSTITUTE**

(Sponsored by Govt. of Puducherry and Affiliated to Pondicherry University, Puducherry)

SERUMAVILANGAI, NEDUNGADU (POST), KARAİKAL - 609 603

**Dr. A. POUCHEPPARADJOU, Ph.D.,
DEAN**

Phone : 04368 - 261372

Fax : 04368-261260

Email : pajancori.kkl@nic.in

QUOTATION CALL LETTER

No: 1509/PAJ/EC/2023

Date: 21-06-2023

Sir,

Sub: PAJANCOA&RI – Engineering Cell – Supply of required materials and Drilling of new borewell to the Department of Plant Pathology for PAJANCOA & RI, Karaikal – Quotations – called for – Reg.

This institute has proposed to Drill a new borewell to the Department of Plant Pathology for PAJANCOA & RI, Karaikal as per the specifications given below.

Sl No.	Item	Specification	Quantity Required.	Rate	Per	Amount
1.		Supply of 150mm dia UPVC plain casing pipe for borewell (Finolex / Jain / Supreme / Truebore / Nandhi) with minimum wall thickness of 6mm..	18.00 Rum			
2.		Labour charges for providing Slot hole in the casing pipe.	Lumpsum			
3.		33.27.11 Supplying transportation and packing of 8mm size down gauge graded pebbles including filling the annular space gradually complete. The pebbles disintegrated pieces should be free from any disintegrated pieces.	3.00 Cum			
4.	Drill a new borewell	33.27.1.1.Drilling of borewell any where in Pondicherry including transportation in alluvial soil, sedimentary strain of clay, sand stone, shale, pebbles, boulders etc. by first taking a pilot bore of 140mm / 150 mm / 200mm and then enlarging to required dia by direct or reverse rotary mud circulation method including fuel, labour for drilling, bentonite mud, water required for drilling at the site, construction of mud pit (water available within a lead of 1.5 Km) using rotary rig - upto 60 mts depth ending below ground level.	18.00 Rum			
5		33.27.2.1. Reaming from 140/150 mm dia pilot bore to 300mm dia bore upto 60 mts depth ending below ground level.	18.00 Rum			
6.		33.27.5 Charges for developing the borewells with air compressor of 600 CFM capacity (minimum 8 hours) including transportation labour and fuel charges for compressor and conducting yield test by "V" Notch methods.	3.00 Hrs			
7.		Transportation charges for all and JCB for digging mudpit	Lumpsum			
8.		Add GST				

You are requested to quote your lowest rate for the Supply of required materials and Drilling of new borewell to the Department of Plant Pathology for PAJANCOA & RI, Karaikal including supplying of required materials with above mentioned specifications. The quotation should be addressed to the DEAN, PAJANCOA & RI,, Nedungadu P.O, Karaikal – 609 603 and should be sent in a sealed cover super scribed as "QUOTATION FOR THE WORK OF Supply of required materials and Drilling of new borewell to the Department of Plant Pathology for PAJANCOA & RI, Karaikal" with due date and time. The quotation should reach this office on or before 4.30 pm on 07-07-2023

Thanking you

Yours faithfully

**Forwarded To Dr. Saravanan.S ASP(CS)
To Upload In Website**

DEAN.