



**PANDIT JAWAHARLAL NEHRU COLLEGE OF AGRICULTURE
AND RESEARCH INSTITUTE, KARAİKAL – 609 603**

(Govt. of Pondicherry institution and Affiliated to the Pondicherry University, Puducherry)

Fax : 091-04368- 261260

Phone: Off : (04368) 261372

: (04368) 261288

E-mail: pajancoa.edu@gmail.com

**Dr.R. SANKAR, Ph.D.,
DEAN i/c**

No. 2144 /PAJ/EC/Block "A"/Ladies Toilet//2025

Date: 19-12-2025

QUOTATION NOTICE

Sub: PAJANCOA&RI – Engineering Cell – Renovation works in ladies toilet at ground floor, Academic Block "A" (Department of Agronomy) for PAJANCOA & RI, Karaikal - Quotations – called for – Reg.

Sealed quotations are invited by the Dean, PAJANCOA & RI, Karaikal, from specialized agencies / eligible contractors for the work of "Renovation works in ladies toilet at ground floor, Academic Block "A" (Department of Agronomy) for PAJANCOA & RI, Karaikal" The quotation should reach this office on or before **4.00 pm on 07-01-2026 and the same will be opened at 4.30 p.m on the same day.**

| S.No. | Description of work | Quantity | Rate | Per | Amount |
|-------|--|----------|------|-----|--------|
| 1 | Dismantling W.C Pan of all sizes including disposal of dismantled materials i/c malba all complete as per the direction of Engineer-in-charge. | 3 Nos | | No | |
| 2. | Dismantling of flushing cistern of all types (C.I / PVC / Vitrous china) including stacking of useful materials near the site and disposal of unserviceable materials within 50 metres lead | 3 Nos | | No | |
| 3. | Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 metres lead - of area 3 sqm and below | 3 Nos | | No | |
| 4. | Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead | 18 Sqm | | Sqm | |
| 5. | Demolishing lime concrete manually / by mechanical means and disposal of material within 50 metres lead as per direction of Engineer-in-charge. | 2 Cum | | Cum | |
| 6. | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - all work upto plith level - 1:5:10 (1 cement : 5 fine aggregate : 10 graded brick aggregate 40mm nominal size) | 2 Cum | | Cum | |
| 7. | Providing and fixing water closet squatting pan (Indian type W.C.pan) with 100 mm Sand Cast Iron P or S trap, 10 litre low level white P.V.C flusing cistren, including flush pipe with, manually controlled device (handle lever) conforming to IS : 7231 , with all fittings and fixtures complete , including cutting and making good the walls and floors wherever required.White vitreous china Onssa pattern W.C pan of size 580x440mm with integral type foot rests | 2 Nos | | No | |
| 8. | Providing and fixing white vitreous china pedestal type water closet (European type W.C.pan) with seat and lid, 10 litre low level white P.V.C. flusing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS: 7231,with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required - W.C. pan with ISI marked white solid plastic seat and lid | 1 No | | No | |
| 9. | Extra for using coloured WC pan with low level cistern of same colour instead of white vitreous china WC pan and cistern | 3 Nos | | No | |
| 10. | Providing and laying ceramic glazed floor tiles of size 300 x 300 mm (thickness to be specified by the manufacturer) , of 1st quality conforming to IS 15622, of approved make , in all colours, shades, except white , ivory, grey, fume red brown, laid on 20 mm thick bed of cement mortar 1:4 (1 cement 4 fine aggregate), jointing with grey cement slurry @ 3.3 kg /sqm including pointing the joints with white cement and matching pigments etc . complete | 18 Sqm | | Sqm | |
| 11 | Providing and fixing vitreous china wash basin including making all connections but excluding the cost of fittings - flat back wash basin of size 630x450mm | 2 Nos | | No | |
| 12. | Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6mm thick hard board ground fixed to wooden cleats with C.P brass screws and washers complete | 2 Nos | | No | |

| S.No. | Description of work | Quantity | Rate | Per | Amount |
|-------|--|----------|------|--------------|--------|
| 13. | Providing and fixing factory made panel PVC door shutter consisting of frame made out of M.S tubes of 19 gauge thickness and size of 19 mm x 19 mm for styles and 15 x15 mm for top & bottom rails. M.S frame shall have a coat of steel primers of approved make and manufacture. M.S. frame covered with 5 mm thick heat moulded PVC 'C' channel of size 30mm thickness, 70 mm width out of which 50 mm shall be flat and 20 mm shall be tapered in 45 degree angle on both side forming styles and 5 mm thick, 95 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm shall be tapered in 45 degree on the inner side to form top and bottom rail and 115 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm shall be tapered on both sides to form lock rail. Top, bottom and lock rails shall be provided both side of the panel. 10mm (5 mm x 2) thick, 20 mm wide cross PVC sheet be provided as gap insert for top rail & bottom rail, panelling of 5 mm thick both side PVC sheet to be fitted in the M.S. frame welded / sealed to the styles & rails with 7 mm (5 mm + 2 mm) thick x 15 mm wide PVC sheet beading on inner side and joined together with solvent cement adhesive. An additional 5 mm thick PVC strip of 20 mm width is to be stuck on the interior side of the 'C' Channel using PVC solvent adhesive etc. complete as per direction of Engineer-in-charge manufacturer's specification & drawing - 30mm thick plain PVC door shutters | 5 Sqm | | Sqm | |
| 14. | Finishing walls with acrylic smooth exterior paint of required shade - New work (two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 0.90 litre / 10 sqm | 150 Sqm | | Sqm | |
| | | | | TOTAL | |

TERMS AND CONDITIONS:-

1. The Earnest Money Deposit should be drawn in favour of the Dean, PAJANCOA & RI and payable at Karaikal in the form of Demand Draft @ 2% of quoted total amount.
2. The rate shall be quoted inclusive of GST, all taxes and transportation charges.
3. The quotation should be addressed to the Dean, PAJANCOA & RI,, Nedungadu P.O, Karaikal – 609 603 and should be sent in a sealed cover super scribed as "QUOTATION FOR THE WORK OF "Renovation works in ladies toilet at ground floor, Academic Block "A" (Department of Agronomy) for PAJANCOA & RI, Karaikal" with due date and time.
4. The undersigned reserves all rights to accept or reject any or all the quotations without assigning any reasons thereof.


DEAN.

To

1. The Institute Website - Dr's's 
2. The Notice Board
3. The Executive Engineer, Engineering Cell, PAJANCOA & RI,
For information and necessary follow up action.