PANDIT JAWAHARLAL NEHRU COLLEGE OF AGRICULTURE AND RESEARCH INSTITUTE, KARAIKAL – 609 603
(Govt. of Pondicherry institution and Affiliated to the Pondicherry University, Puducherry)
Fax : 091-04368- 261260
Phone: Off : (04368) 261372
: (04368) 261288
E-mail: pajancoa.edu@ gmail.com

Dr.A. POUCHEPPARADJOU, Ph.D.,
DEAN.

No: 2282 /PAJ/EE/EC/2026 Date: 13-11-2026

QUOTATION NOTICE

Sub: PAJANCOA&RI – Engineering Cell – Renovation works at Bath and Toilet (A-Block East side – G.F) in the Girls Hostel for PAJANCOA & RI, Karaikal- Quotations – called for – Reg.

Sealed quotations are invited by the Dean, PAJANCOA & RI, Karaikal, from specialized agencies / eligible contractors for the work of "**Renovation works at Bath and Toilet (A-Block East side – G.F) in the Girls Hostel for PAJANCOA & RI, Karaikal"** The quotation should reach this office on or before **4.00 pm on 25-11-2026 and the same will be opened at 4.30 p.m on the same day.**

S.No.	Description of work	Quantity	Rate	Per	Amount
1	Dismantling W.C.Pan of all sizes including disposal of dismantled materials i/c malba all complete as per the direction of Engineer-in-charge.	4.00 Nos		Each	
2.	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead	50.00 sqm		sqm	
3.	Demolishing cement concrete manually / by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-in-charge. - Nominal concrete 1:4:8 or leaner mix (including equivalent design mix)	11.00 cum		cum	
4.	Supplying and filling with gravel (excluding rock) in trenches plinth, sides of foundations etc . In layers not exceeding 20 cm in depth consolidating each deposited layers by ramming and watering etc .complete including all lead and lift	11.00 cum		cum	
5.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - all work upto plith level - 1:3:6 (1 cement : 3 fine aggregate : 6 graded stone aggregate 20mm nominal size)	7.25 Cum		Cum	
6.	Repairs to plaster of thickness 12mm to 20mm in patches of area 2.5 sq.metres and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete including disposal of rubbish to the dumping ground as per direction of Engineer-in-charge with cement mortar 1:4 (1 cement : 4fine aggregate)	11.00 sqm		sqm	
7.	Providing and fixing water closet squatting pan (Indian type W.C.pan) with 100 mm Sand Cast Iron P or S trap, 10 litre low level white P.V.C flusing cistren, including flush pipe with, manually controlled device (handle lever) conforming to IS : 7231 , with all fittings and fixtures complete , including cutting and making good the walls and floors wherever required. White vitreous china Orissa pattern W.C.pan of size 580x440mm with integral type foot rests.	3.00 Nos		each	

S.No.	Description of work	Quantity	Rate	Per	Amount
8.	Providing and fixing white vitreous china pedestal type water closet (European type W.C.pan) with seat and lid, 10 litre low level white P.V.C. flusing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS: 7231,with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required -W.C. pan with ISI marked white solid plastic seat and lid	1.00 No		Each	
9.	Extra for using coloured W.C.pan instead of white W.C.pan.	4.00 No		Each	
10.	Providing and laying vitrified floor tiles of size 600 x600 mm (thickeness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622 of approved make , in all colours and shades, laid on 20 mm thick cement mortar 1:4 (1 cement : 4 fine aggregate) ,jointing with grey cement slurry @3.3 kg per sqm including grouting the joints with white cement and matching pigments etc., complete - size of tile600x600mm	50.00 Sqm		Sqm	
11	Providing and fixing colour vitreous china wash basin including making all connections but excluding the cost of fittings - flat back wash basin of size 630x450mm	4.00 Nos		each	
12	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6mm thick hard board ground fixed to wooden cleats with C.P.brass screws and washers complete	4.00 Nos		each	
13.	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content - with water thinnable cement primer on wall surface having VOC content less than 50 grams / litre	130.00 sqm		sqm	
14.	Finishing walls with acrylic smooth exterior paint of required shade - New work (two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 0.90 litre / 10 sqm	130.00 sqm		sqm	
15.	Painting with synthetic enamel paint of approved brand and manufacutre to give an even shade - Two or more coats on new work	140.00 sqm		sqm	
			TOTAL		

TERMS AND CONDITIONS:-

1. The Earnest Money Deposit should be drawn in favor of the Dean, PAJANCOA & RI and payable at Karaikal in the form of Demand Draft @ 2% of quoted total amount.
2. The rate shall be quoted inclusive of GST, all taxes and transportation charges.
3. The quotation should be addressed to the Dean, PAJANCOA & RI,, Nedungadu P.O, Karaikal – 609 603 and should be sent in a sealed cover super scribed as "**QUOTATION FOR THE WORK OF "Renovation works at Bath and Toilet (A-Block East side – G.F) in the Girls Hostel for PAJANCOA & RI, Karaikal"**" with due date and time.
4. The undersigned reserves all rights to accept or reject any or all the quotations without assigning any reasons thereof.

DEAN. 16/11/24

To

1. The Institute Website
2. The Notice Board
3. The Executive Engineer, Engineering Cell, PAJANCOA &RI, For information and necessary follow up action.