PANDIT JAWAHARLAL NEHRU COLLEGE OF AGRICULTURE
AND RESEARCH INSTITUTE, KARAIKAL – 609 603
(Govt. of Pondicherry institution and Affiliated to the Pondicherry University, Puducherry)
Fax : 091-04368- 261260
Phone: Off : (04368) 261372
: (04368) 261288
E-mail: pajancoa.edu@ gmail.com

Dr.A. POUCHEPPARADJOU, Ph.D.,
DEAN.

No: 2231 /PAJ/EE/EC/2026 Date: 13-11-2026

QUOTATION NOTICE

Sub: PAJANCOA&RI – Engineering Cell – Renovation works at Guest Room in the Girls Hostel for PAJANCOA & RI, Karaikal Quotations – called for – Reg.

& & & &

Sealed quotations are invited by the Dean, PAJANCOA & RI, Karaikal, from specialized agencies / eligible contractors for the work of "**Renovation works at Guest Room in the Girls Hostel for PAJANCOA & RI, Karaikal"** The quotation should reach this office on or before **4.00 pm on 25-11-2026 and the same will be opened at 4.30 p.m on the same day.**

S.No.	Description of work	Quantity	Rate	Per	Amount
1	Chipping of unsound / weak concrete material from slabs ,beams , columns etc with manual Chisel and / or by standard power driven percussion type or of approved make including tapering of all edges , making square shoulders of cavities including cleaning the exposed concrete surface and reinforcement with wire brushes etc. and disposal of debris for all lead and lifts all complete as per direction of Engineer-in charge - 25 mm average thickness	45.00 sqm		sqm	
2.	Dismantling W.C.Pan of all sizes including disposal of dismantled materials i/c melba all complete as per the direction of Engineer-in-charge.	1.00 Nos		Each	
3.	Dismantling of flushing cistern of all types (C.I / PVC / Vitreous china) including stacking of useful materials near the site and disposal of unserviceable materials within 50 meters lead	1.00 Nos		Each	
4.	Demolishing lime concrete manually / by mechanical means and disposal of material within 50 meters lead as per direction of Engineer-in-charge	1.00 Cum		Cum	
5.	Supplying and applying bituminous solution primer on roof and or wall surface at 0..24 liter per square meter	45.00 Sqm		Sqm	
6.	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - all work up to plinth level - 1:3:6 (1 cement : 3 fine aggregate : 6 graded stone aggregate 20mm nominal size)	1.00 Cum		Cum	
7.	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 3.5 in foundation and plinth in cement mortar 1:4 (1 cement : 4 fine aggregate)	1.50 Cum		Cum	
8.	Providing and laying vitrified floor tiles of size 600 x600 mm (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622 of approved make , in all colours and shades, laid on 20 mm thick cement mortar 1:4 (1 cement : 4 fine aggregate) ,jointing with grey cement slurry @3.3 kg per sqm including grouting the joints with white cement and matching pigments etc., complete - size of tile600x600mm	20.00 Sqm		Sqm	

S.No.	Description of work	Quantity	Rate	Per	Amount
9.	Providing and fixing Ist quality ceramic glazed wall tiles conforming to IS:15622(thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved, in skirting, risers of steps and dados, over 12mm thick bed of cement mortar 1:3 (1 cement : 3 fine aggregate) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete	45.00 Sqm		Sqm	
10.	Finishing walls with water proofing cement paint of required shade - New work (Two or more coats applied @ 3.84 kg / 10 sqm)	20.00 sqm		sqm	
11	20mm cement plaster of mix 1.4 (1 cement : 4 fine aggregate)	12.00 Sqm		Sqm	
12	Providing and fixing white vitreous china pedestal type water closet (European type W.C.pan) with seat and lid, 10 liter low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS. 7231,with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required -W.C. pan with ISI marked white solid plastic seat and lid	1.00 No		Each	
13.	Extra for using coloured W.C.pan instead of white W.C.pan	1.00 No		Each	
14.	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams / liter , of approved brand and manufacturer, including applying additional coats wherever required, to achieve even shade and color - Two coats	20.00 Sqm		Sqm	
			TOTAL		

TERMS AND CONDITIONS:-

1. The Earnest Money Deposit should be drawn in favor of the Dean, PAJANCOA & RI and payable at Karaikal in the form of Demand Draft @ 2% of quoted total amount.
2. The rate shall be quoted inclusive of GST, all taxes and transportation charges.
3. The quotation should be addressed to the Dean, PAJANCOA & RI,, Nedungadu P.O, Karaikal – 609 603 and should be sent in a sealed cover super scribed as "**Renovation works at Guest Room in the Girls Hostel for PAJANCOA & RI, Karaikal"** with due date and time.
4. The undersigned reserves all rights to accept or reject any or all the quotations without assigning any reasons thereof.

DEAN. 16/11/26

To

1. The Institute Website
2. The Notice Board
3. The Executive Engineer, Engineering Cell, PAJANCOA &RI,

For information and necessary follow up action.